Constructing Officials' Quarters for six School Masters at Kallurkatte, Nagar Taluk.

Items of works	Per.	Main building of two quarters in one block	Out house for one quarters	Total
Clearing site levelling ground	L. S.	Rs.		
Earthwork excavating foundations	C. yd.	57	9	66
Burnt stone in mortar filling foundation	C. ft.	2,774	341	3,115
Burnt brick in mortar superstructure	„	4,198	95	4,293
Burnt stone slabs, 5" and 6" thick, dressed and fixed ...	S. ft.	581	30	611
Cuddappah stone slabs, 2" thick for sill of doors and windows	„	„	„	„
Teakwood work wrought and put up	C. ft.	126·0	16·30	142·30
Roofing with 1st class Mangalore tiles on teak reepers including chunam borders.	Sq.	27·72	4·25	32·00
Plastering with mortar	„	65·22	10·37	75·50
Flooring with Cuddappah slabs on 3" concrete and cement pointing.	„	2·46	0·80	3·26
Paving Mangalore floor tiles, 9" sqr. ...	„	9·60	„	9·60
Filling concrete for floors and plastered with mortar ...	„	1·60	0·75	2·35
Teakwood battened door with necessary fittings ...	S. ft.	319	„	319
Teakwood battened windows with ¾" iron bars and necessary fittings.	„	120	9	129
Chacolate painting, inclusive verandah	Sq.	11·32	0·52	11·84
Tarring	„	5·75	2·00	7·75
Constructing small and big cisterns both in bath and kitchen.	L. S.	Rs.		
Mangalore ridge tiles set in mortar	R. ft.	132	22	154
Pointing with chunam	Sq.	430	0·65	4·95
Mangalore ventilating tiles	Each	20	2	22
Dressing verandah pittars and cutting grooves ...	L. S.	Rs.		
Teakwood eave board, (9"×1"), ordinary	R. ft.	184	46	230
Burnt brick in clay superstructure ...	C. ft.	...	456	456
Teakwood ledged door	S. ft.	..	23	23
Teakwood ventilators with cross iron bars ...	„		3	3
Whitewashing	Sq.	65.22	10·37	75·59
Similar blocks 2. Total 3 Blocks.				

N.B.—All works estimated L. S. should be done at usual or tendered rates for various kinds of works as per instructions on the spot by the officers in charge.

V. R. NIJAGAL,
Executive Engineer.

CHITALDRUG DIVISION.

Dated 24th May 1918.

"The attention of contractors is drawn to advertisement dated 30th March 1918, *vide* pages 279 and 280, Part IV of *Mysore Gazette*, dated 4th April 1918, calling for tenders for constructing a kitchen block for the High School Students' Home at Chitaldrug. Tenders will be received up to 10th June 1918."

N. ANANDALVAR,
Executive Engineer.

DISTRICT, MUNICIPAL AND LOCAL BOARDS.

TUMKUR DISTRICT.

Abstract Notification dated 12th May 1918.

It is hereby notified for general information that the right of collecting toll on carts entering the Municipality of Tiptur for a period of one year from 1st July 1918 to the 30th June 1919, will be sold by public auction by the Assistant Commissioner, Gubbi Sub-Division, or other officer deputed for the purpose by the Deputy Commissioner at the Tiptur Taluk Office at 2 o'clock on Tuesday the 18th June 1918.

	Rs.	a.	p.
1. On a double bullock cart, laden	0	2	0
2. Do empty	0	1	0
3 On a single bullock cart, laden or empty ...	0	1	0

For the conditions of sale, *vide* previous issue of the *Mysore Gazette.*

Abstract Notification dated 12th May 1918.

It is hereby notified for general information that the right of collecting tolls at the toll-gate at Nidasale on the Tumkur-Maddur road for twelve months from 1st July 1918 to 30th June 1919, will be sold by public auction at the Taluk Office, Kunigal, on 19th June 1918, at 2 P.M., by the President, District Board, or other officer appointed by the Deputy Commissioner for the purpose.

For the rates of toll and the conditions of sale, *vide* previous issue of the *Mysore Gazette.*

A. SUBRAMANYA IYER,
President of Municipalities.